

**Truro Heights Road Sewer Upgrade
Truro Heights, Nova Scotia**

1. Instruction to Tenderers .1 Note the inclusion of this addendum on the Tender Form (Section 00 41 43, Article 2.3)

2. Drawing C-07 .1 For clarification of the notes on the Sewer Pipe Trench Section 1:
 - Reinstatement of disturbed areas of existing asphalt driveways is to be 75mm of asphalt.
 - Reinstatement of disturbed areas of existing gravel driveways is to be 100mm of Type 1 gravel.
 - Reinstatement of the gravel shoulder is to be 450mm of type 2 gravel and 150mm of Type 1 gravel.
 - Ditch excavation is required only to the extent necessary for pipe installation trenching and is to be reinstated to the existing elevation. Disturbed ditch areas are to be reinstated with hydroseed and hay mulch. Disturbed lawn areas are to be reinstated with topsoil and sod.
 - Existing culverts are to be removed only as needed for pipe installation trenching and are to be reinstated (not replaced).

***** END OF ADDENDUM #1 *****